


Running CRYRING with uncompensated electron cooler solenoid

Claude Krantz


CRYRING@ESR Users Meeting

19 August 2022



Machine study:
Understand coupling of betatron motion introduced by the cooler solenoid, and the importance of its cancellation by YR11MO1P.

Electron-cooler




“Compensation solenoid”
(YR11MO1P)

Uses ~ 1 m of beamline real-estate (together with Schottky electrodes)


Prelude: Betatron motion

Stored ions do not follow the design orbit precisely (“divergence”).

Need **quadrupole magnets** to “bend back” their trajectories every now and then.






Mane et al., Rep. Prog. Phys. 68 (2005)



www.mpi-hd.mpg.de



Prelude: Betatron motion

If, in a certain place of the ring, we observed **transverse position and velocity** of a specific ion over many revolutions ...



Prelude: Betatron motion



If, in a certain place of the ring, we observed **transverse position and velocity** of a specific ion over many revolutions ...



... we'd find that all measured coordinates enclose an **elliptic volume** of (x, v_x) phase-space.

- *Reminds of a harmonic oscillator!*
- **“Betatron oscillation”**

Prelude: Betatron motion



Some “characteristic ion” circles a larger ellipse than 95% of its peers:



Enclosed area / $\pi = \epsilon_{95\%}$ (beam emittance)

Projection onto x-axis:

→ “2- σ beam diameter”

Prelude: Betatron motion

In a “text book” storage ring, betatron oscillations along x and y are considered *independent!*




Prelude: Betatron motion


The phase advances between two passages of an ion define the **horizontal and vertical “tunes”** Q_x and Q_y :

$$Q_{x,y} = \frac{1}{2\pi} \oint_{1\text{turn}} d\varphi_{x,y}$$

“Working point”: (Q_x, Q_y)



Prelude: Betatron motion



Working point (Q_x, Q_y) :

Chosen in a way to prevent **resonance** of revolution and betatron motions.



Standard working point of CRYRING:

$$(Q_x, Q_y) = (2.42, 2.42)$$

Betatron coupling by cooler solenoid


The electron cooler uses a longitudinal magnetic field for guiding its electrons.

Energy transfer between betatron motions in horizontal (x) and vertical (y) planes!




Betatron coupling by cooler solenoid


M.-T. Tang et al., arXiv:1508.02472v1 (2015)




Energy transfer between betatron motions in horizontal (x) and vertical (y) planes!



„Pulsing“ of horizontal and vertical emittances.




Tunes become *undefined* in vicinity of coupling resonances.




Wiedemann, Particle Accelerator Physics, 2015



Betatron coupling by cooler solenoid



YR11MO1P
 “counteracting”
 solenoid: equal $|BL|$,
 inverted polarity



YR03MO3C
 electron guiding field
 (0.01 ... 0.10 T,
 typ. 0.03 T)



Ion motions in horizontal and vertical plane again independent of each other!

Quantify amount of betatron coupling:

How much (additional) coupling if YR11MO1P is disabled?

Is there significant betatron coupling from other sources?

Stability and intensity of stored beams:

Are acceptance and storage affected by betatron coupling?

Quality of electron-cooled beams:

Can the cooler be set-up equally well?

Are cooling rates or final beam sizes affected?

D⁺, injected at 300 keV/u (3...5 μA) from local source.

For measurements **without electron cooling**: acceleration to **1 MeV/u (0.29 Tm)**
(compromise between sensitivity to solenoid fields and reasonable beam lifetime).


With electron cooling: acceleration to **2 MeV/u (0.41 Tm)**
(to avoid running at low-limit of 20-kV HV supply)

All measurements close to **design machine tune** (Q_h, Q_v) = (2.42, 2.42).

Method of closest tune approach


Vary the settings of the quadrupole magnets in a way to scan the working point across the coupling resonance.

→ “Distance of closest approach” ΔQ of the measured tunes quantifies the coupling strength.



Wiedemann, Particle Accelerator Physics, 2015

Tunes become *undefined* in vicinity of coupling resonance.




Tune measurements: RF-Knock-Out

Apply a transverse
(horizontal or vertical)
RF kicker field.

If RF signal and betatron
motion are in phase,
kicks add up.

- Blow-up of betatron amplitudes.
- Particles lost from acceptance.



Betatron coupling

Tune measurements: RF-Knock-Out



FM of RF-KO exciter ($\sim 1 \text{ s}^{-1}$)

Step-wise beam loss observed at resonance conditions.

storage time

14:47:01 - INFO [04 May 2022 12:47:01,752] (FeignDecoder.java) - Response from the node: [CMW-DIR-LOCAL], request count: [7], response count: [7]






Betatron coupling

Cooler solenoid @ 200 G
(but no electron cooling)

+

compensation solenoid **disabled**.

Cooler magnets @ 200 G, Comp. Solenoid OFF, Sextupoles OFF





Betatron coupling

Cooler solenoid @ 300 G
(but no electron cooling)

+

compensation solenoid **disabled**.

Cooler magnets @ 300 G, Comp. Solenoid OFF, Sextupoles OFF





Betatron coupling

Cooler solenoid @ 300 G
(but no electron cooling)

+

compensation solenoid **enabled**.

Cooler magnets @ 300 G, Comp. Solenoid ON, Sextupoles OFF'





→ Compensation seems near-perfect!

Intensity and stability

Varied working point at injection **and** on 1-MeV/u flattop.



No cooling, no chromaticity correction




Intensity and stability



Varied working point at injection **and** on 1-MeV/u flattop.

No cooling, no chromaticity correction



No obvious effect on storage at $Q_x \approx Q_y$.







For small **relative ion velocity** $\mathbf{u} = (u_x, u_y, u_z)$:
 “damping” force $\mathbf{F} \sim \mathbf{u}$:

$$F_{x,y} \approx -a_{x,y} \cdot u_{x,y} \quad (\text{trans.})$$

$$F_z \approx -a_z \cdot u_z \quad (\text{long.})$$

Electron cooling



For small **relative ion velocity** $\mathbf{u} = (u_x, u_y, u_z)$:
 “damping” force $\mathbf{F} \sim \mathbf{u}$:

$$\mathbf{F} \approx -a \cdot \mathbf{u} \quad \text{with}$$

$$a \sim \frac{Z_{\text{ion}}^2 n_e}{T_e^{3/2}}$$

← “Effective
electron
temperature”

“Effective temperature” of electron beam

Defines:

Maxima of cooling force at $|u| \sim \sqrt{\frac{k T_e}{m_e}}$

Damping rate for $|u| \ll \sqrt{\frac{k T_e}{m_e}}$


Sources of T_e :

Hot cathode.

Cooling/heating during e-beam formation + transport.

Magnetic field imperfections.

Alignment errors.





For small relative ion velocity $\mathbf{u} = (u_x, u_y, u_z)$:
 “damping” force $\mathbf{F} \sim -\mathbf{u}$:

$$\mathbf{F} \approx -a \cdot \mathbf{u} \quad \text{with}$$

$$a \sim \frac{Z_{ion}^2 n_e}{T_e^{3/2}}$$

← “Effective electron temperature”




Electron cooling









Alignment of electron and ion beams:

Observation of ion beam response on IPMs.







(ionisation beam profile monitors)



Electron cooling



Electron cooling




The *apparently weaker beam response* could make optimal alignment of the cooler practically more difficult ...

→ **Idea:**


- 1) Set-up electron cooling with compensation solenoid **disabled and enabled**, starting with the more “difficult” case.
- 2) Measure *electron cooler performance* for both cases.

Longitudinal cooling force measurement: “Bunch phase shift method”

Cooler velocity **matched** to rf-bunched ions





Cooler velocity **detuned** from bunch velocity



$$F_{\text{cool}}(\Delta v) = Z_{\text{ion}} e U_{\text{RF}} \sin(\Delta\phi) / L_{\text{cool}}$$




Compensation solenoid
disabled:

Compensation solenoid
enabled:





→ No difference observed!

Electron cooling



Transverse cooling force for small amplitudes: $F \sim u$:



$$F \approx -a \cdot u \quad \text{with}$$


$$a \sim \frac{Z_{ion}^2 n_e}{T_e^{3/2}}$$

→ All betatron amplitudes damped at the same rate λ .


→ Beam envelopes evolve as

$$\sigma(t) = A_0 \exp(-\lambda t) + \sigma_\infty$$

Compensation solenoid
disabled:



Compensation solenoid
enabled:





→ No difference observed!

Additional remarks

By chance, found a long-standing bug in computation of chromaticity correction.

$$\xi = \frac{dQ}{d(\delta p/p)}$$


→ *Much improved momentum acceptance with new sextupole magnet settings.*



Additional remarks

“Re-discovered” a significant offset between the working point programmed via accelerator controls and the true measured tunes.

→ Still being worked on ...



Additional remarks





Compensation solenoid contains the **Schottky pickups** of CRYRING.

→ *Very important diagnostics for operation with and experiments on coasting beams!!*

Measurement of e-beam space-charge potential

Checking stability of ion momenta during DR experiments.



We tested CRYRING operation with the **cooler compensation solenoid YR11MO1P disabled**.

The effect of **betatron coupling is clearly observed** in the beam response to transverse excitations (by RF-KO or cooler).

The **standard W.P. becomes undefined**, as predicted by calculations.

No adverse effect on **storage stability**.

No effect on **quality of electron cooling**.

If enabled, **YR11MO1P seems to compensate** betatron coupling *perfectly*.

Tentative verdict:

Unless for the most exotic beam manipulations (1-D excitation ...), we can probably run just fine without YR11MO1P, if a new Schottky detector is installed.

Z. Andelkovic, U. Clausen, S. Fedotova,
W. Geithner, F. Herfurth, R. Heß,
C. K., S. Khammee, I. Kraus, A. Reiter,
B. Rück, S. Trotsenko, G. Vorobjev